



Community Development Department
16220 Wausau Ave. | South Holland, Illinois 60473
Phone: 708-210-2900 | Fax: 708-210-2959
www.southholland.org

Removing an Inground Swimming Pool

- The pool and all materials must be removed and disposed of properly.
- This includes all walls, floors, drains, additional plumbing and electric.
- An inspection is required once all the materials have been removed.
- The ground is to be compacted/tamped down.
- Clean gravel is to be placed and compacted at a minimum 12" (1-foot).
- An inspection is required prior to adding the black dirt.
- Filtering landscape cloth is to be placed on the compacted gravel prior to adding black dirt.
- Compaction of the black dirt is to take place every 12".
- Top Soil is to be used for the top 4-6" of fill to ensure proper growth of grass or gardening. If the plan is to add trees, additional black dirt depth may be necessary.
- A final inspection is required once the job is completed.
- An approved permit is required prior to beginning work.